

ADDENDUM NO. 3

CRAIG HIGH SCHOOL BIOMASS PROJECT

TO: ALL PLANHOLDERS

Date: March 17, 2023

.....
The following information is provided to the potential Bidders for the above named Project and shall become a part of the bidding and contract documents, dated 12.9.22. No consideration will be allowed due to any potential Bidder not being aware of or familiar with this addendum.

The Bidder must acknowledge receipt of this addendum on its Bid Proposal Form in order for its Bid to be deemed acceptable. This addendum shall form part of the Invitation to Bid (IFB) and is to be read, interpreted, and coordinated with all other parts. The Addendum No. 1 contains 1 page in total and (1) PDF attachments titled “Supplied Components from Twin Heat” containing 1 page.

.....
Description of addendum:

ELECTRICAL:

1. **CLARIFICATION: ELECTRICAL DEMOLITION:**

- A. All existing electrical on the East Wall and North wall of existing shop in the area of the new boiler room shall be removed entirely and the feeders being removed back to the next branch device outside this space or all the way back to Existing S2 panel if a dedicated circuit.
- B. All existing overhead ceiling receptacles of the existing shop in the area of the new boiler room shall be removed entirely and the feeders being removed back to the next branch device outside this space or all the way back to Existing S2 panel if a dedicated circuit.
- C. Existing lighting wiring shall be removed as required based on the new switching setup required.
- D. Panel S2 shall be removed and replaced with a new panel in the same spot. Contractor shall confirm that breaker locations and ampacities match up with the existing panel.

MECHANICAL:

2. **CLARIFICATION – WOOD BOILER SYSTEM**

The list of the boiler components that has already been procured by the owner is listed on the last sheet of the project drawings that have been supplied with the IFB. For reference, that sheet is attached to this addendum. See attached “Supplied Components from Twin Heat.pdf”

CIVIL:

3. **C1.0: ASPHALT PATCHING**

Concrete will be an acceptable material in lieu of asphalt to patch the trench in the parking area if it is found that asphalt is not available on the island. However, please bid out as asphalt at this time.